| | | | | | | |
|---|---|---|---|---|---|---|
| 7 | Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. | Sqm | 124.4 | 876.68 | Rupees Eight Hundred Seventy Six and Sixty Eight Paise Only | 109058.99 |
| 8 | Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. complete as per specifications. | Sqm | 139.95 | 1517.28 | Rupees One Thousand Five Hundred Seventeen and Twenty Eight Paise Only | 212343.34 |
| 9 | Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. | Sqm | 2170 | 2.46 | Rupees Two and Forty Six Paise Only | 5338.20 |
| 10 | Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam Specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density Complete as per Specifications. | Cum | 542.5 | 1063.08 | Rupees One Thousand Sixty Three and Eight Paise Only | 576720.90 |
| 11 | Providing, laying and rolling with vibratory roller of built-up spray grout layer over prepared base consisting of a two layer composite construction of compacted crushed coarse aggregates using motor grader for aggregates. Key stone chips spreader may be used with application of bituminous binder after each layer, and with key aggregates placed on top of the second layer to serve as a base confirming to the line, grades and cross-section specified, the compacted layer thickness being 75mm Complete as per specifications. | Sqm | 217 | 255.02 | Rupees Two Hundred Fifty Five and Two Paise Only | 55339.34 |
| 12 | Providing and applying tack coat on the prepared black topped surfaces at 5kg per 10 sqm, heating bitumen in boiler fitted with spray set (Excluding cleaning of road surface) including cost of all Materials, labour, HOM of machineries complete as per specifications. | Sqm | 2170 | 20.59 | Rupees Twenty and Fifty Nine Paise Only | 44680.30 |

B-T-Ramteke

Signature of the Contractor

Executive Engine